

JAERI-M
8 7 6 3

格納容器圧力抑制系信頼性実証試験
データレポート・4 (TEST 1101)

1980年3月

久木田 豊・生田目 健・山本 信夫・斯波 正誼

日本原子力研究所
Japan Atomic Energy Research Institute

この報告書は、日本原子力研究所が JAERI-M レポートとして、不定期に刊行している研究報告書です。入手、複製などのお問い合わせは、日本原子力研究所技術情報部（茨城県那珂郡東海村）あて、お申しこしください。

JAERI-M reports, issued irregularly, describe the results of research works carried out in JAERI. Inquiries about the availability of reports and their reproduction should be addressed to Division of Technical Information, Japan Atomic Energy Research Institute, Tokai-mura, Naka-gun, Ibaraki-ken, Japan.

格納容器圧力抑制系信頼性実証試験
データレポート・4 (TEST 1101)

日本原子力研究所東海研究所安全工学部
久木田豊・生田目健・山本信夫・斯波正謙

(1980年2月4日受理)

格納容器圧力抑制系信頼性実証試験は、LOCA時にBWR用Mark II格納容器圧力抑制系に発生すると予想される熱水力現象に関する試験を行い、格納容器信頼性の実証に資するデータを得ることを目的としている。試験装置の体積縮小率は1/18であり、ウェットウェル部は実炉のウェットウェルの実物大20°セクタ模型である。

本報告は、昭和54年3月30日に実施したTEST 1101のデータ報告である。本試験は、原研による最初の公式試験であり、破断口径200mmの水放出試験である。得られたドライウェル初期圧力上昇率は約155 kPa/s、ペント管内最大蒸気重量速度は約100 kg/m²-sであった。

本試験計画は、電源開発促進対策特別事業の一環として科学技術庁より原研に委託されたものである。

本報告は先に作成した原研所内資料J A E R I - memo 8325(1979年7月)の内容に検討・修正を加え公開に付するものである。

JAERI-M 8763

Full-Scale Mark II CRT Program
Data Report No. 4 (TEST 1101)

Yutaka KUKITA, Ken NAMATAME
Nobuo YAMAMOTO and Masayoshi SHIBA

Division of Reactor Safety,
Tokai Research Establishment, JAERI

(Received February 4, 1980)

The Full-Scale Mark II CRT (Containment Response Test) Program^{*} was initiated in 1977 to provide a data base for evaluation of the LOCA hydrodynamic loads for the Mark II pressure suppression system. The test facility is 1/18 in volume and has a wetwell which is a full-scale replica of one 20°-sector of that of a reference Mark II.

TEST 1101 is a large (200 mm) water break test performed on March 30, 1979. The test conditions were similar to those for TEST 0004 performed on February 28, 1979, except for small alterations in pool initial temperature and depth. Though the test was performed for a supernominal break area (approx. 160 % of the scaled break area for a postulated double-ended break in the recirculation line), the obtained drywell initial pressurization rate (155 kPa/s) was smaller than the safety analysis value for the reference Mark II.

Keywords : BWR, LOCA, Pressure Suppression, Mark II Containment, Hydrodynamic Loads, Full-Scale Test, Data

* Work performed under the auspices of the Atomic Energy Bureau, the Science and Technology Agency of Japan.

This report supersedes JAERI internal document JAERI-memo 8325 (July 1979).

目 次

1. まえがき	1
2. 試験装置	2
3. 試験条件と試験結果	34
謝 辞	35
試験データ	44

Contents

1. Introduction	1
2. Test Facility and Test Instrumentation	2
3. Test Conditions and Test Results	34
Acknowledgement	35
Long Term Plots of Data	44
Short Term Plots of Data	89

List of Tables

Table

- 2. 1 Comparison of Major Design Parameters
- 2. 2 Summary of Data Channels
- 2. 3 Summary of Data Acquisition Systems
- 2. 4 Identification of Data Channels
- 2. 5 List of Data Channels (Computer Recorded Channels)
- 2. 6 List of Data Channels (PCM Track-1 Channels)
- 2. 7 List of Data Channels (PCM Track-2 Channels)
- 2. 8 State of Measurement Equipment (Computer Recorded Channels)
- 2. 9 State of Measurement Equipment (PCM Track-1 Channels)
- 2.10 State of Measurement Equipment (PCM Track-2 Channels)
- 2.11 Calibration Data
- 2.12 Measurement Ranges

- 3. 1 Test Matrix
- 3. 2 Test Specifications
- 3. 3 Summary of Data Recording
- 3. 4 Initial and Final Conditions

List of Figures

Figure

- 2. 1 Schematic Flow Diagram of Test Facility
- 2. 2 Transducer Locations for Primary System
- 2. 3 Transducer Locations for Drywell
- 2. 4 Transducer Locations for Wetwell (Plan View)
- 2. 5 Transducer Locations for Vent Pipes and Thermocouple Locations for Wetwell
- 2. 6 Pressure and Differential Pressure Transducer Locations for Wetwell
- 2. 7 Water Level Detector and Phase Boundary Detector Locations for Wetwell
- 2. 8 Locations of Strain Gages
- 2. 9 Locations of Accelerometers

- 3. 1 Operation Records
- 3. 2 Initial Temperature Distribution in Primary System
- 3. 3 Initial and Final Temperature Distributions in Drywell
- 3. 4 Initial and Final Temperature Distributions in Wetwell

1. まえがき

格納容器圧力抑制系信頼性実証試験は、わが国の最新型沸騰水型炉に使用されているMark II格納容器における冷却材喪失事故時の熱水力現象を模擬した試験を行い、格納容器の信頼性実証に資するデータを得ることを目的としている。本試験計画は、電源開発促進対策事業の一環として、科学技術庁より原研に委託されたものであり、昭和52年度を初年度として5年間にわたり実施される予定である。原研内では、安全工学部安全工学第1研究室が試験計画の立案および試験結果の解析を担当し、同安全試験技術室が試験装置の建設、運転、管理を担当している。試験装置は昭和54年3月原研東海研究所敷地内に完成し、以後1カ月に約1回の割合で試験を実施している。

本報告書は、昭和54年3月30日に実施したTEST 1101のデータ報告である。本試験は、原研による最初の公式試験であり、昭和54年2月28日に実施した試験装置検収試験TEST 0004とほぼ同様な条件による大口径(200mm)水放出試験であって、運転要員の慣熟と試験結果の再現性の確認を目的としている。破断面積は幾何学的スケーリングによる値より過大に設定したが、得られたドライウェル初期圧力上昇率は参考炉の評価値を下回った。

2. 試験装置

試験装置の概略を Fig. 2.1 に示す。試験装置主要部は試験格納容器、圧力容器、放出配管等により構成される。試験格納容器ウェットウェル部は、1100 MWe 級 Mark II 格納容器のウェットウェルの中心角 20° の 1 セクタを模擬したものであり、各部の高さ、内部のペント管等の寸法は実炉とほぼ同一である。ドライウェル、1 次系の容積は、実炉の相当部分の約 1/18 である。これらの諸元を Table 2.1 に示す。

本試験装置における計測の項目を Table 2.2 に、計測チャンネルリストおよび計測点位置を Table 2.5 ~ 2.7 および Fig. 2.2 ~ 2.9 に示す。データは 2 系統の収録装置によって収録する。比較的変化の遅い信号（温度、水位計出力等）は小型計算機により 1 チャンネルあたり 50 data/s のサンプリング速度で収録する。一方、比較的変化の速い信号（圧力、歪、加速度等）は PCM (Pulse Code Modulation) 方式により 455.55 data/s のサンプリング速度で収録し、試験後、小型計算機を介してデータを再編集する。以後の処理はいずれも原研計算センターの大型計算機によって行う。データ収録装置の主要諸元を Table 2.3 に示す。

本試験における計測器の動作状態を Table 2.8 ~ 2.10 に、圧力・差圧変換器の較正係数を Table 2.11 に、計測レンジの設定値を Table 2.12 に示す。

本試験に先立ち 2 月 18 日から 28 日にかけて、計 4 回の試験装置検収試験を実施した。この過程で変換器の絶縁不良をはじめとする障害が発生したが、これらは本試験の開始前にすべて補修を完了した。本試験においては特に大きな計測上の障害は発生しなかったが、ウェットウェルの水位計 80 チャンネルのうち 23 チャンネルに関しては、コネクタの接触不良等のため試験データを得ることができなかった。

試験装置本体に関しても大きな障害は発生しなかったが、放出開始直前に圧力容器予備ノズルからわずかな漏洩を生じた。




Fig. 2.1 Schematic Flow Diagram of Test Facility

Table 2.1 Comparison of Major Design Parameters

Parameter		Reference Mark II	CRT Facility
<hr/>			
<u>Drywell</u>			
Free Volume, Including Air Volumes in Vent Pipes	(m ³)	5700	329
<u>Vent Pipe</u>			
Number	(-)	108	7
Length	(m)	14.2	13.6
Clearance, to Pool Bottom	(m)	3.66	3.66
Number of Vacuum Breakers	(-)	11	1
<u>Wetwell</u>			
Free Volume	(m ³)	4100	255
Water Volume	(m ³)	3200	188
Height, to Diaphragm Floor	(m)	17.3	17.0
<u>Pressure Vessel</u>			
Inside Diameter	(m)	6.4	2.2
Height	(m)	22.0	10.4

Table 2.2 Summary of Data Channels

Location	Item	Data Acquisition		PCM Track-1	PCM Track-2
		Computer	PCM		
Pressure Vessel	Pressure	2			
	Diff. Press.	6			
	Temperature	6			
Blowdown Pipe	Water Level	6			
	Pressure	2			
	Diff. Press.	1			
Drywell	Temperature	3		2	2
	Timing Sig.	2		1	
	Pressure	1			
Vent Pipe	Temperature	8			
	Water Level	4			
	Pressure	9			
Wetwell	Temperature	6			
	Water Level	19		4	4
	Strain				
	Acceleration				
	Timing Sig.	1		20	
	Pressure	1			
	Diff. Press.	2			
	Temperature	32			
	Water Level	80			
	Acceleration			15	12
	Timing Sig.				
	Pressure				

Table 2.4 Identification of Data Channels

Channel Code = A B C D - E F G

A, B Location

- = P V Pressure Vessel
- = B P Blowdown Pipe
- = D W Drywell
- = V P Vent Pipe
- = W W Wetwell

C Measurement Item

- = P Pressure
- = D Differential Pressure
- = T Temperature
- = L Water Level Signal
- = S Strain
- = A Acceleration
- = M Actuation Signal

D Data Acquisition System

- = S Computer Recorded , 50 data/s
- = F PCM Recorded , 455.6 data/s

E Group Number

Computer	PCM System
192	39 x 2 tracks

F G Sequential Number

+10.00	+10.00
-4.883	-19.53
50.00	455.56
0.028	0.0488

Table 2.3 Summary of Data Acquisition Systems

Max. Number of Channels	(V)
Input Range	(mV/digit)
Resolution	(data/ch./s)
Sampling Rate	(ms/ch.)
Skew	

Table 2.5 List of Data channels (Computer Recorded Channels)

Channel No.	Channel Code	Measurement Location
1	BPMS-001	RUPTURE DISC BREAK SIGNAL
2	BPMS-002	MAIN DISCHARGE VALVE CLOSE SIGNAL
3	VPMS-001	OPENING OF VACUUM BREAKER (5-STEPS)
4		
5	BPPS-001	BLOWDOWN PIPE (8.4M FROM OUTL.)
6	PVPS-002	VESSEL STEAM DOME
7	PVPS-001	VESSEL STEAM DOME
8	BPPS-002	BLOWDOWN PIPE (0.9M FROM OUTL.)
9	DWPS-001	DRYWELL
10	WWPS-001	WETWELL AIRSPACE (15.0M ABOVE BOTT.)
11		
12	PVDS-001	DP OVER VESSEL (EL = 0.0M - +9.2M)
13	PVDS-002	DP OVER VESSEL (EL = 0.0M - +2.6M)
14	PVDS-003	DP OVER VESSEL (EL = +2.2M - +4.2M)
15	PVDS-004	DP OVER VESSEL (EL = +3.8M - +5.8M)
16	PVDS-005	DP OVER VESSEL (EL = +5.4M - +7.4M)
17	PVDS-006	DP OVER VESSEL (EL = +7.0M - +9.2M)
18	BPDS-001	DYNAMIC PRESS. IN BLOWDOWN PIPE
19	WWDS-001	DP OVER POOL (EL = 4.5M - 15.5M)
20	WWDS-002	DP ACROSS DIAPHRAGM FLOOR
21		
22	PVTS-001	VESSEL (EL = 0.6M)
23	PVTS-002	VESSEL (EL = 2.2M)
24	PVTS-003	VESSEL (EL = 3.8M)
25	PVTS-004	VESSEL (EL = 5.4M)
26	PVTS-005	VESSEL (EL = 7.0M)
27	PVTS-006	VESSEL (EL = 8.6M)
28	BPTS-001	BLOWDOWN PIPE (6.5M FROM OUTL.)
29	BPTS-002	BLOWDOWN PIPE (4.1M FROM OUTL.)
30	BPTS-003	BLOWDOWN PIPE (0.9M FROM OUTL.)
31	DWTS-101	DRYWELL (0.5M ABOVE DF)
32	DWTS-102	DRYWELL (2.5M ABOVE DF)
33	DWTS-103	DRYWELL (4.5M ABOVE DF)
34	DWTS-201	DRYWELL (0.5M ABOVE DF)
35	DWTS-202	DRYWELL (2.5M ABOVE DF)
36	DWTS-203	DRYWELL (4.5M ABOVE DF)
37	DWTS-301	DRYWELL (0.5M ABOVE DF)
38	DWTS-302	DRYWELL (3.5M ABOVE DF)
39	VPTS-101	VP1 (0.5M ABOVE OUTL.)
40	VPTS-102	VP1 (11.5M ABOVE OUTL.)
41	VPTS-201	VP2 (0.5M ABOVE OUTL.)
42	VPTS-202	VP2 (11.5M ABOVE OUTL.)
43	VPTS-301	VP3 (0.5M ABOVE OUTL.)
44	VPTS-302	VP3 (11.5M ABOVE OUTL.)
45	WWTS-101	WETWELL (T1, 1.0M ABOVE BOTT.)
46	WWTS-102	WETWELL (T1, 3.0M ABOVE BOTT.)
47	WWTS-103	WETWELL (T1, 5.0M ABOVE BOTT.)
48	WWTS-104	WETWELL (T1, 7.0M ABOVE BOTT.)
49	WWTS-105	WETWELL (T1, 9.0M ABOVE BOTT.)
50	WWTS-106	WETWELL (T1, 11.0M ABOVE BOTT.)
51	WWTS-107	WETWELL (T1, 13.0M ABOVE BOTT.)
52	WWTS-108	WETWELL (T1, 15.0M ABOVE BOTT.)

Table 2.5 (Continued)

Channel No.	Channel Code	Measurement Location
53	WWTS-201	WETWELL (T2, 1.0M ABOVE BOTT.)
54	WWTS-202	WETWELL (T2, 3.0M ABOVE BOTT.)
55	WWTS-203	WETWELL (T2, 5.0M ABOVE BOTT.)
56	WWTS-204	WETWELL (T2, 7.0M ABOVE BOTT.)
57	WWTS-205	WETWELL (T2, 9.0M ABOVE BOTT.)
58	WWTS-206	WETWELL (T2, 11.0M ABOVE BOTT.)
59	WWTS-207	WETWELL (T2, 13.0M ABOVE BOTT.)
60	WWTS-208	WETWELL (T2, 15.0M ABOVE BOTT.)
61	WWTS-301	WETWELL (T3, 1.0M ABOVE BOTT.)
62	WWTS-302	WETWELL (T3, 3.0M ABOVE BOTT.)
63	WWTS-303	WETWELL (T3, 5.0M ABOVE BOTT.)
64	WWTS-304	WETWELL (T3, 7.0M ABOVE BOTT.)
65	WWTS-305	WETWELL (T3, 9.0M ABOVE BOTT.)
66	WWTS-306	WETWELL (T3, 11.0M ABOVE BOTT.)
67	WWTS-307	WETWELL (T3, 13.0M ABOVE BOTT.)
68	WWTS-308	WETWELL (T3, 15.0M ABOVE BOTT.)
69	WWTS-401	WETWELL (T4, 1.0M ABOVE BOTT.)
70	WWTS-402	WETWELL (T4, 3.0M ABOVE BOTT.)
71	WWTS-403	WETWELL (T4, 5.0M ABOVE BOTT.)
72	WWTS-404	WETWELL (T4, 7.0M ABOVE BOTT.)
73	WWTS-405	WETWELL (T4, 9.0M ABOVE BOTT.)
74	WWTS-406	WETWELL (T4, 11.0M ABOVE BOTT.)
75	WWTS-407	WETWELL (T4, 13.0M ABOVE BOTT.)
76	WWTS-408	WETWELL (T4, 15.0M ABOVE BOTT.)
77		
78	PVLS-001	VESSEL (EL = 0.6M)
79	PVLS-002	VESSEL (EL = 2.2M)
80	PVLS-003	VESSEL (EL = 3.8M)
81	PVLS-004	VESSEL (EL = 5.4M)
82	PVLS-005	VESSEL (EL = 7.0M)
83	PVLS-006	VESSEL (EL = 8.6M)
84	DWLS-001	DRYWELL (0.048M ABOVE DF)
85	DWLS-002	DRYWELL (0.096M ABOVE DF)
86	DWLS-003	DRYWELL (0.144M ABOVE DF)
87	DWLS-004	DRYWELL (0.192M ABOVE DF)
88	VPLS-101	VP1 (0.042M ABOVE OUTL.)
89	VPLS-103	VP1 (2.042M ABOVE OUTL.)
90	VPLS-105	VP1 (4.042M ABOVE OUTL.)
91	VPLS-201	VP2 (0.042M ABOVE OUTL.)
92	VPLS-203	VP2 (2.042M ABOVE OUTL.)
93	VPLS-205	VP2 (4.042M ABOVE OUTL.)
94	VPLS-301	VP3 (0.042M ABOVE OUTL.)
95	VPLS-302	VP3 (1.042M ABOVE OUTL.)
96	VPLS-303	VP3 (2.042M ABOVE OUTL.)
97	VPLS-304	VP3 (3.042M ABOVE OUTL.)
98	VPLS-305	VP3 (4.042M ABOVE OUTL.)
99	VPLS-401	VP4 (0.042M ABOVE OUTL.)
100	VPLS-403	VP4 (2.042M ABOVE OUTL.)
101	VPLS-405	VP4 (4.042M ABOVE OUTL.)
102	VPLS-501	VP5 (0.042M ABOVE OUTL.)
103	VPLS-502	VP5 (1.042M ABOVE OUTL.)
104	VPLS-503	VP5 (2.042M ABOVE OUTL.)
105	VPLS-504	VP5 (3.042M ABOVE OUTL.)
106	VPLS-505	VP5 (4.042M ABOVE OUTL.)

Table 2.5 (Continued)

Channel No.	Channel Code	Measurement Location
107	WWLS-104	WETWELL (L1, 5.75M ABOVE BOTT.)
108	WWLS-105	WETWELL (L1, 6.50M ABOVE BOTT.)
109	WWLS-106	WETWELL (L1, 7.25M ABOVE BOTT.)
110	WWLS-107	WETWELL (L1, 8.00M ABOVE BOTT.)
111	WWLS-108	WETWELL (L1, 8.75M ABOVE BOTT.)
112	WWLS-109	WETWELL (L1, 9.50M ABOVE BOTT.)
113	WWLS-110	WETWELL (L1, 10.25M ABOVE BOTT.)
114	WWLS-111	WETWELL (L1, 11.00M ABOVE BOTT.)
115	WWLS-112	WETWELL (L1, 11.75M ABOVE BOTT.)
116	WWLS-113	WETWELL (L1, 12.50M ABOVE BOTT.)
117	WWLS-114	WETWELL (L1, 13.25M ABOVE BOTT.)
118	WWLS-115	WETWELL (L1, 14.00M ABOVE BOTT.)
119	WWLS-116	WETWELL (L1, 14.75M ABOVE BOTT.)
120	WWLS-201	WETWELL (L2, 3.50M ABOVE BOTT.)
121	WWLS-202	WETWELL (L2, 4.25M ABOVE BOTT.)
122	WWLS-203	WETWELL (L2, 5.00M ABOVE BOTT.)
123	WWLS-204	WETWELL (L2, 5.75M ABOVE BOTT.)
124	WWLS-205	WETWELL (L2, 6.50M ABOVE BOTT.)
125	WWLS-206	WETWELL (L2, 7.25M ABOVE BOTT.)
126	WWLS-207	WETWELL (L2, 8.00M ABOVE BOTT.)
127	WWLS-208	WETWELL (L2, 8.75M ABOVE BOTT.)
128	WWLS-209	WETWELL (L2, 9.50M ABOVE BOTT.)
129	WWLS-210	WETWELL (L2, 10.25M ABOVE BOTT.)
130	WWLS-211	WETWELL (L2, 11.00M ABOVE BOTT.)
131	WWLS-212	WETWELL (L2, 11.75M ABOVE BOTT.)
132	WWLS-213	WETWELL (L2, 12.50M ABOVE BOTT.)
133	WWLS-214	WETWELL (L2, 13.25M ABOVE BOTT.)
134	WWLS-215	WETWELL (L2, 14.00M ABOVE BOTT.)
135	WWLS-216	WETWELL (L2, 14.75M ABOVE BOTT.)
136	WWLS-303	WETWELL (L3, 5.00M ABOVE BOTT.)
137	WWLS-305	WETWELL (L3, 6.50M ABOVE BOTT.)
138	WWLS-307	WETWELL (L3, 8.00M ABOVE BOTT.)
139	WWLS-309	WETWELL (L3, 9.50M ABOVE BOTT.)
140	WWLS-311	WETWELL (L3, 11.00M ABOVE BOTT.)
141	WWLS-313	WETWELL (L3, 12.50M ABOVE BOTT.)
142	WWLS-315	WETWELL (L3, 14.00M ABOVE BOTT.)
143	WWLS-401	WETWELL (L4, 3.50M ABOVE BOTT.)
144	WWLS-402	WETWELL (L4, 4.25M ABOVE BOTT.)
145	WWLS-403	WETWELL (L4, 5.00M ABOVE BOTT.)
146	WWLS-404	WETWELL (L4, 5.75M ABOVE BOTT.)
147	WWLS-405	WETWELL (L4, 6.50M ABOVE BOTT.)
148	WWLS-406	WETWELL (L4, 7.25M ABOVE BOTT.)
149	WWLS-407	WETWELL (L4, 8.00M ABOVE BOTT.)
150	WWLS-408	WETWELL (L4, 8.75M ABOVE BOTT.)
151	WWLS-409	WETWELL (L4, 9.50M ABOVE BOTT.)
152	WWLS-410	WETWELL (L4, 10.25M ABOVE BOTT.)
153	WWLS-411	WETWELL (L4, 11.00M ABOVE BOTT.)
154	WWLS-412	WETWELL (L4, 11.75M ABOVE BOTT.)
155	WWLS-413	WETWELL (L4, 12.50M ABOVE BOTT.)
156	WWLS-414	WETWELL (L4, 13.25M ABOVE BOTT.)
157	WWLS-415	WETWELL (L4, 14.00M ABOVE BOTT.)
158	WWLS-416	WETWELL (L4, 14.75M ABOVE BOTT.)
159	WWLS-503	WETWELL (L5, 5.00M ABOVE BOTT.)
160	WWLS-505	WETWELL (L5, 6.50M ABOVE BOTT.)

Table 2.5 (Continued)

Channel No.	Channel Code	Measurement Location
161	WWLS-507	WETWELL (L5, 8,00M ABOVE BOTT.)
162	WWLS-509	WETWELL (L5, 9,50M ABOVE BOTT.)
163	WWLS-511	WETWELL (L5, 11,00M ABOVE BOTT.)
164	WWLS-513	WETWELL (L5, 12,50M ABOVE BOTT.)
165	WWLS-515	WETWELL (L5, 14,00M ABOVE BOTT.)
166	WWLS-604	WETWELL (L6, 5,75M ABOVE BOTT.)
167	WWLS-606	WETWELL (L6, 7,25M ABOVE BOTT.)
168	WWLS-608	WETWELL (L6, 8,75M ABOVE BOTT.)
169	WWLS-610	WETWELL (L6, 10,25M ABOVE BOTT.)
170	WWLS-612	WETWELL (L6, 11,75M ABOVE BOTT.)
171	WWLS-614	WETWELL (L6, 13,25M ABOVE BOTT.)
172	WWLS-616	WETWELL (L6, 14,75M ABOVE BOTT.)
173	WWLS-704	WETWELL (L7, 5,75M ABOVE BOTT.)
174	WWLS-706	WETWELL (L7, 7,25M ABOVE BOTT.)
175	WWLS-708	WETWELL (L7, 8,75M ABOVE BOTT.)
176	WWLS-710	WETWELL (L7, 10,25M ABOVE BOTT.)
177	WWLS-712	WETWELL (L7, 11,75M ABOVE BOTT.)
178	WWLS-714	WETWELL (L7, 13,25M ABOVE BOTT.)
179	WWLS-716	WETWELL (L7, 14,75M ABOVE BOTT.)
180	WWLS-804	WETWELL (L8, 5,75M ABOVE BOTT.)
181	WWLS-806	WETWELL (L8, 7,25M ABOVE BOTT.)
182	WWLS-808	WETWELL (L8, 8,75M ABOVE BOTT.)
183	WWLS-810	WETWELL (L8, 10,25M ABOVE BOTT.)
184	WWLS-812	WETWELL (L8, 11,75M ABOVE BOTT.)
185	WWLS-814	WETWELL (L8, 13,25M ABOVE BOTT.)
186	WWLS-816	WETWELL (L8, 14,75M ABOVE BOTT.)
187		
188		
189		
190		
191		
192		

Table 2.6 List of Data Channels (PCM Track-1 Channels)

Channel No.	Channel Code	Measurement Location
1	BPMF-001	RUPTURE DISC BREAK SIGNAL
2	BPMF-002	MAIN DISCHARGE VALVE CLOSE SIGNAL
3		
4	DWPF-001	DRYWELL
5	VPPF-101	VP1 (0.5M ABOVE OUTL.)
6	VPPF-201	VP2 (0.5M ABOVE OUTL.)
7	VPPF-301	VP3 (0.5M ABOVE OUTL.)
8	VPPF-302	VP3 (6.0M ABOVE OUTL.)
9	VPPF-303	VP3 (11.5M ABOVE OUTL.)
10	VPPF-401	VP4 (0.5M ABOVE OUTL.)
11	VPPF-501	VP5 (0.5M ABOVE OUTL.)
12	VPPF-502	VP5 (6.0M ABOVE OUTL.)
13	VPPF-503	VP5 (11.5M ABOVE OUTL.)
14	WWPF-101	POOL BOTT., UNDER VP1
15	WWPF-102	POOL BOTT., UNDER VP2
16	WWPF-103	POOL BOTT., UNDER VP3
17	WWPF-104	POOL BOTT., UNDER VP4
18	WWPF-105	POOL BOTT., UNDER VP5
19	WWPF-106	POOL BOTT., BETW, VP1, VP6 & PEDESTAL
20	WWPF-107	POOL BOTT., BETW, VP2 & VP3
21	WWPF-201	WALL BESIDE VP2 (P1, 1.8M ABOVE BOTT.)
22	WWPF-202	WALL BESIDE VP2 (P1, 3.6M ABOVE BOTT.)
23	WWPF-203	WALL BESIDE VP2 (P1, 6.0M ABOVE BOTT.)
24	WWPF-301	WALL BESIDE VP3 (P2, 1.8M ABOVE BOTT.)
25	WWPF-302	WALL BESIDE VP3 (P2, 3.6M ABOVE BOTT.)
26	WWPF-303	WALL BESIDE VP3 (P2, 6.0M ABOVE BOTT.)
27	WWPF-401	SHELL BESIDE VP3 (P3, 1.8M ABOVE BOTT.)
28	WWPF-402	SHELL BESIDE VP3 (P3, 3.6M ABOVE BOTT.)
29	WWPF-501	SHELL BESIDE VP4 (P4, 1.8M ABOVE BOTT.)
30	WWPF-502	SHELL BESIDE VP4 (P4, 3.6M ABOVE BOTT.)
31	WWPF-602	WALL BESIDE VP4 (P5, 3.6M ABOVE BOTT.)
32	WWPF-702	WALL BESIDE VP7 (P6, 3.6M ABOVE BOTT.)
33	WWPF-001	WETWELL AIRSPACE (15.0M ABOVE BOTT.)
34		
35	VPSF-101	LOWER BRACE BETW, VP1 & WALL
36	VPSF-102	LOWER BRACE BETW, VP1 & VP2
37	VPSF-103	LOWER BRACE BETW, VP1 & VP6
38	VPSF-201	UPPER BRACE BETW, VP1 & PEDESTAL
39		

Table 2.7 List of Data Channels (PCM Track-2 Channels)

Channel No.	Channel Code	Measurement Location
1	BPMF-001	RUPTURE DISC BREAK SIGNAL
2	BPMF-002	MAIN DISCHARGE VALVE CLOSE SIGNAL
3		
4	VPAF-101	VP2 OUTL., (0DEG)
5	VPAF-102	VP2 OUTL., (90DEG)
6	VPAF-201	VP5 OUTL., (0DEG)
7	VPAF-202	VP5 OUTL., (90DEG)
8	WWAF-001	POOL BOTT., UNDER VP5
9	WWAF-002	POOL BOTT., BETW, VP2, VP3, VP4 & VP7
10	WWAF-003	WALL BESIDE VP2 (3.0M ABOVE BOTT.)
11	WWAF-004	WALL BESIDE VP7 (3.0M ABOVE BOTT.)
12	WWAF-005	SHELL BESIDE VP3 (3.0M ABOVE BOTT.)
13	WWAF-006	SHELL BESIDE VP3 (6.0M ABOVE BOTT.)
14	WWAF-007	SHELL BESIDE VP4 (3.0M ABOVE BOTT.)
15	WWAF-008	SHELL BESIDE VP4 (6.0M ABOVE BOTT.)
16	WWAF-009	PEDESTAL (3.0M ABOVE BOTT.)
17	WWAF-010	PEDESTAL (6.0M ABOVE BOTT.)
18	WWAF-011	SHELL AT DF LEVEL (0DEG)
19	WWAF-012	SHELL AT DF LEVEL (90DEG)
20		
21	WWLF-101	PHASE BDRY, (0.9M BELOW OUTL., CENTER)
22	WWLF-102	PHASE BDRY, (0.9M BELOW OUTL., 0DEG)
23	WWLF-104	PHASE BDRY, (0.9M BELOW OUTL., 90DEG)
24	WWLF-106	PHASE BDRY, (0.9M BELOW OUTL., 180DEG)
25	WWLF-108	PHASE BDRY, (0.9M BELOW OUTL., 270DEG)
26	WWLF-201	PHASE BDRY, (0.6M BELOW OUTL., CENTER)
27	WWLF-203	PHASE BDRY, (0.6M BELOW OUTL., 45DEG)
28	WWLF-205	PHASE BDRY, (0.6M BELOW OUTL., 135DEG)
29	WWLF-207	PHASE BDRY, (0.6M BELOW OUTL., 225DEG)
30	WWLF-209	PHASE BDRY, (0.6M BELOW OUTL., 315DEG)
31	WWLF-301	PHASE BDRY, (0.3M BELOW OUTL., CENTER)
32	WWLF-302	PHASE BDRY, (0.3M BELOW OUTL., 0DEG)
33	WWLF-304	PHASE BDRY, (0.3M BELOW OUTL., 90DEG)
34	WWLF-306	PHASE BDRY, (0.3M BELOW OUTL., 180DEG)
35	WWLF-308	PHASE BDRY, (0.3M BELOW OUTL., 270DEG)
36		
37		
38		
39		




Fig. 2.2 Transducer Locations for Primary System


PLAN VIEW

Fig. 2.3 Transducer Location for Drywell




Fig. 2.4 Transducer Locations for Wetwell (Plan View)




Fig. 2.5 Transducer Location for Vent Pipes and Thermocouple Locations for Wetwell




Fig. 2.6 Pressure and Differential Pressure Transducer Locations for Wet well 1




Fig. 2.7 Water Level Detector and Phase Boundary Detector Locations for Wetwell




Fig. 2.8 Locations of Strain Gages

1 : Strain Gages (4 pts)




Fig. 2.9 Locations of Accelerometers

Table 2.8 State of Measurement Equipments (Computer Recorded Channels)

Channel No.	Channel Code	Acceptability o Yes <input checked="" type="checkbox"/> No	Remarks
1	BPMS-001	o	
2	BPMS-002	o	Spurious signal after 1.9sec.
3	VPMS-001	o	
4			
5	BPPS-001	o	
6	PVPS-002	o	
7	PVPS-001	o	
8	BPPS-002	o	
9	DWPS-001	o	
10	WWPS-001	o	
11			
12	PVDS-001	o	
13	PVDS-002	o	
14	PVDS-003	o	
15	PVDS-004	o	Unreliable during 24-60sec.
16	PVDS-005	o	
17	PVDS-006	o	
18	BPDS-001	<input checked="" type="checkbox"/>	Unreliable
19	WWDS-001	o	
20	WWDS-002	o	Temporarily saturated
21			
22	PVTS-001	o	
23	PVTS-002	o	
24	PVTS-003	o	
25	PVTS-004	o	
26	PVTS-005	o	
27	PVTS-006	o	
28	BPTS-001	o	
29	BPTS-002	o	
30	BPTS-003	o	

Table 2.8 (continued)

Channel No.	Channel Code	Acceptability o Yes <input checked="" type="checkbox"/> No	Remarks
31	DWTS-101	o	
32	DWTS-102	o	
33	DWTS-103	o	
34	DWTS-201	o	
35	DWTS-202	o	
36	DWTS-203	o	
37	DWTS-301	o	
38	DWTS-302	o	
39	VPTS-101	o	
40	VPTS-102	o	
41	VPTS-201	o	
42	VPTS-202	o	
43	VPTS-301	o	
44	VPTS-302	o	
45	WWTS-101	o	
46	WWTS-102	o	
47	WWTS-103	o	
48	WWTS-104	o	
49	WWTS-105	o	Wetted during pool swell
50	WWTS-106	o	Wetted during pool swell
51	WWTS-107	o	
52	WWTS-108	o	
53	WWTS-201	o	
54	WWTS-202	o	
55	WWTS-203	o	
56	WWTS-204	o	
57	WWTS-205	o	Wetted during pool swell
58	WWTS-206	o	Wetted during pool swell
59	WWTS-207	o	
60	WWTS-208	o	

Table 2.8 (continued)

Channel No.	Channel Code	Acceptability o Yes <input checked="" type="checkbox"/> No	Remarks
61	WWTS-301	o	
62	WWTS-302	o	
63	WWTS-303	o	
64	WWTS-304	o	
65	WWTS-305	o	Wetted during pool swell
66	WWTS-306	o	Wetted during pool swell
67	WWTS-307	o	
68	WWTS-308	o	
69	WWTS-401	o	
70	WWTS-402	o	
71	WWTS-403	o	
72	WWTS-404	o	
73	WWTS-405	o	Wetted during pool swell
74	WWTS-406	o	Wetted during pool swell
75	WWTS-407	o	
76	WWTS-408	o	
77			
78	PVLS-001	o	
79	PVLS-002	o	
80	PVLS-003	o	
81	PVLS-004	o	
82	PVLS-005	o	
83	PVLS-006	o	
84	DWLS-001	o	
85	DWLS-002	o	
86	DWLS-003	o	
87	DWLS-004	o	
88	VPLS-101	o	
89	VPLS-103	o	
90	VPLS-105	o	

Table 2.8 (continued)

Channel No.	Channel Code	Acceptability o Yes o No	Remarks
91	VPLS-201	o	
92	VPLS-203	o	
93	VPLS-205	o	
94	VPLS-301	o	
95	VPLS-302	o	
96	VPLS-303	o	
97	VPLS-304	o	
98	VPLS-305	o	
99	VPLS-401	o	
100	VPLS-403	o	
101	VPLS-405	o	
102	VPLS-501	o	
103	VPLS-502	o	
104	VPLS-503	o	
105	VPLS-504	o	
106	VPLS-505	o	
107	WWLS-104	o	
108	WWLS-105	o	
109	WWLS-106	o	
110	WWLS-107	o	
111	WWLS-108	o	
112	WWLS-109	o	
113	WWLS-110	o	
114	WWLS-111	o	
115	WWLS-112	o	
116	WWLS-113	o	
117	WWLS-114	o	
118	WWLS-115	o	
119	WWLS-116	o	
120	WWLS-201	o	

Table 2.8 (continued)

Channel No.	Channel Code	Acceptability o Yes d No	Remarks
121	WWLS-202	o	
122	WWLS-203	o	
123	WWLS-204	o	
124	WWLS-205	o	
125	WWLS-206	o	
126	WWLS-207	o	
127	WWLS-208	o	
128	WWLS-209	o	
129	WWLS-210	o	
130	WWLS-211	d	Cable connector failure
131	WWLS-212	o	
132	WWLS-213	o	
133	WWLS-214	o	
134	WWLS-215	o	
135	WWLS-216	d	Spurious signal
136	WWLS-303	o	
137	WWLS-305	o	
138	WWLS-307	o	
139	WWLS-309	o	
140	WWLS-311	o	
141	WWLS-313	o	
142	WWLS-315	o	
143	WWLS-401	d	
144	WWLS-402	d	
145	WWLS-403	d	
146	WWLS-404	d	Cable connector failure
147	WWLS-405	d	
148	WWLS-406	d	
149	WWLS-407	d	
150	WWLS-408	d	

Table 2.8 (continued)

Channel No.	Channel Code	Acceptability o Yes ø No	Remarks
151	WWLS-409	ø	
152	WWLS-410	ø	
153	WWLS-411	ø	
154	WWLS-412	ø	
155	WWLS-413	ø	Cable connector failure
156	WWLS-414	ø	
157	WWLS-415	ø	
158	WWLS-416	ø	
159	WWLS-503	ø	
160	WWLS-505	o	
161	WWLS-507	o	
162	WWLS-509	ø	Cable connector failure
163	WWLS-511	o	
164	WWLS-513	ø	Cable connector failure
165	WWLS-515	o	
166	WWLS-604	ø	Cable connector failure
167	WWLS-606	o	
168	WWLS-608	o	
169	WWLS-610	o	
170	WWLS-612	ø	Cable connector failure
171	WWLS-614	o	
172	WWLS-616	o	
173	WWLS-704	o	
174	WWLS-706	o	
175	WWLS-708	o	
176	WWLS-710	o	
177	WWLS-712	o	
178	WWLS-714	o	
179	WWLS-716	o	
180	WWLS-804	o	

Table 2.8 (continued)

Channel No.	Channel Code	Acceptability o Yes p No	Remarks
181	WWLS-806	o	
182	WWLS-808	o	
183	WWLS-810	o	
184	WWLS-812	o	
185	WWLS-814	o	
186	WWLS-816	o	
187			
188			
189			
190			
191			
192			

Table 2.9 State of Measurement Equipments (PCM Track-1 Channels)

Channel No.	Channel No.	Acceptability o Yes ø No	Remarks
1	BPMF-001	o	
2	BPMF-002	o	
3			
4	DWPF-001	o	
5	VPPF-101	o	
6	VPPF-201	o	
7	VPPF-301	o	
8	VPPF-302	o	
9	VPPF-303	o	
10	VPPF-401	o	
11	VPPF-501	o	
12	VPPF-502	o	
13	VPPF-503	o	
14	WWPF-101	o	
15	WWPF-102	o	
16	WWPF-103	o	
17	WWPF-104	o	
18	WWPF-105	o	
19	WWPF-106	o	
20	WWPF-107	o	
21	WWPF-201	o	
22	WWPF-202	o	
23	WWPF-203	o	
24	WWPF-301	o	
25	WWPF-302	o	
26	WWPF-303	o	
27	WWPF-401	o	
28	WWPF-402	o	
29	WWPF-501	o	
30	WWPF-502	o	

Table 2.9 (continued)

Channel No.	Channel Code	Acceptability o Yes <input checked="" type="checkbox"/> No	Remarks
31	WWPF-602	o	,
32	WWPF-702	o	
33	WWPF-001	o	
34			
35	VPSF-101	o	
36	VPSF-102	o	
37	VPSF-103	<input checked="" type="checkbox"/>	Sensor failure.
38	VPSF-201	o	
39			

Table 2.10 State of Measurement Equipments (PCM Track-2 Channels)

Channel No.	Channel Code	Acceptability o Yes ø No	Remarks
1	BPMF-001	o	
2	BPMF-002	o	
3			
4	VPAF-101	o	
5	VPAF-102	ø	Spurious signal
6	VPAF-201	o	
7	VPAF-202	o	
8	WWAF-001	ø	Unreasonable data.
9	WWAF-002	ø	Unreasonable data.
10	WWAF-003	ø	Unreasonable data.
11	WWAF-004	ø	Unreasonable data.
12	WWAF-005	o	
13	WWAF-006	o	
14	WWAF-007	o	
15	WWAF-008	o	
16	WWAF-009	o	
17	WWAF-010	o	
18	WWAF-011	o	
19	WWAF-012	o	
20			
21	WWLF-101	o	
22	WWLF-102	o	
23	WWLF-104	ø	Cable failure
24	WWLF-106	o	
25	WWLF-108	o	
26	WWLF-201	ø	
27	WWLF-203	ø	Cable failure
28	WWLF-205	ø	
29	WWLF-207	o	
30	WWLF-209	o	

Table 2.10 (continued)

Channel No.	Channel Code	Acceptability o Yes <input checked="" type="checkbox"/> No	Remarks
31	WWLF-301	o	
32	WWLF-302	o	
33	WWLF-304	o	
34	WWLF-306	<input checked="" type="checkbox"/>	Cable failure
35	WWLF-308	o	
36			
37			
38			
39			

Table 2.11 Calibration Data

PRESSURE CHANNELS (COMPUTER RECORDED)

DIFFERENTIAL PRESSURE CHANNELS (COMPUTER RECORDED)

<u>Pressure Vessel</u>	Date of Calibration	Mar. 26, 1979
	Calibration Conducted by	Filling Water into Vessel.
<u>Test Containment</u>	Date of Calibration	Feb. 24, 1979
	Calibration Conducted by:	
	<input type="checkbox"/> Filling Water into Containment	
	<input checked="" type="checkbox"/> Applying Known Pressure on Transducer	
<u>Pressure Vessel</u>	Date of Calibration	Mar. 26, 1979
	Range of Calibration Pressure (kPa)	101 - 7348
	Water Level in Pressure Vessel (m)	Full
<u>Test Containment</u>	Date of Calibration	Mar. 27, 1979
	Range of Calibration Pressure (kPa)	101 - 476
	Water Level in Wetwell (m)	7.3

Channel No.	Channel Code	kPa/Digit	Max. Deviation kPa
System Computer			
5	BPPS-001	4.911	20.4
6	PVPS-002	4.782	17.2
7	PVPS-001	4.807	19.1
8	BPPS-002	4.844	41.6
9	DWPS-001	0.2395	2.9
10	WWPS-001	0.2392	4.9

Channel No.	Channel Code	kPa/Digit	Max. Deviation kPa
System Computer			
12	PVDS-001	0.04850	
13	PVDS-002	0.02426	
14	PVDS-003	0.02436	
15	PVDS-004	0.02415	
16	PVDS-005	0.02399	
17	PVDS-006	0.02400	
18	BPDS-001	2.461	
19	WWDS-001	0.04451	
20	WWDS-002	0.05365	

PRESSURE CHANNELS (PCM RECORDED)

Table 2.11 (Continued)

Test Containment		Mar. 27, 1979	
Date of Calibration	Range of Calibration Pressure (kPa)	101 - 476	
Water Level in Wetwell	(m)	7.3	

Channel No.	Channel Code	kPa/Digit	Max. Deviation kPa
PCM Track-1			
4	DMPF-001	0.9521	
5	VPPF-101	0.9485	
6	VPPF-201	0.9605	
7	VPPF-301	0.9643	
8	VPPF-302	0.9602	
9	VPPF-303	0.9496	
10	VPPF-401	0.9596	
11	VPPF-501	0.9512	
12	VPPF-502	0.9558	
13	VPPF-503	0.9558	
14	WMPF-101	0.9549	
15	WMPF-102	0.9519	
16	WMPF-103	0.9577	

Channel No.	Channel Code	kPa/Digit	Max. Deviation kPa
PCM Track-1			
17	WMPF-104	0.9596	
18	WMPF-105	0.9615	
19	WMPF-106	0.9605	
20	WMPF-107	0.9549	
21	WMPF-201	0.9630	
22	WMPF-202	0.9549	
23	WMPF-203	0.9687	
24	WMPF-301	0.9531	
25	WMPF-302	0.9506	
26	WMPF-303	0.9540	
27	WMPF-401	0.9568	
28	WMPF-402	0.9540	
29	WMPF-501	0.9615	
30	WMPF-502	0.9549	
31	WMPF-602	0.9531	
32	WMPF-702	0.9605	
33	WMPF-001	0.9454	

Table 2.12 Measurement Ranges

Ch. No.	1) Item	1) Location	Measurement Range			LPF Cut-Off Freq. (Hz)
			Manufacturer's Specification for Transducer	Expected Overall Range	Unit	
Computer Recorded Channels						
5 - 8	P	PV/BP	101 - 9908	101 - 10000	kPa	100
9	P	DW	0 - 591	0 - 600 ²⁾	kPa	100
10	P	WW	0 - 591	0 - 600 ²⁾	kPa	100
12	D	PV	0 - 98.1	0 - 100	kPa	100
13 - 17	D	PV	0 - 49	0 - 50	kPa	100
18	D	BP	0 - 4904	0 - 4950	kPa	100
19	D	WW	0 - 98.1	0 - 100	kPa	100
20	D	DW-WW	0 - 98.1	0 - 100	kPa	100
22 - 30	T	PV/BP		0 - 300	°C	250
31 - 38	T	DW		0 - 150	°C	250
39 - 44	T	VP		0 - 150	°C	250
45 - 76	T	WW		0 - 150	°C	250
PCM Track-1 Channels						
4	P	DW	0 - 591	0 - 600	kPa	250
5 - 33	P	WW	0 - 591	0 - 600	kPa	250
34 - 38	S	VP		-2300 - +2300	μm/m	250
PCM Track-2 Channels						
4 - 7	A	VP	-980 - +980 ³⁾	-980 - +980	m/s ²	300
8 - 19	A	WW	-980 - +980 ³⁾	-196 - +196	m/s ²	300

Notes:

- 1) For meanings of the abbreviations see Table 2.5.
- 2) Linear response of transducers beyond manufacturer-specified range was expected.
- 3) Range for transducer and charge preamplifier.

3. 試験条件と試験結果

TEST 1101は原研による最初の公式試験であり、先に株式会社日立製作所によって行われた試験装置の第4回検収試験と同様な破断口径200mmの水放出試験である。ただし本試験においては圧力抑制プールの初期水位が0.22m低く、プール初期温度が約20°C高い。本試験は主としてプールスウェルに関するデータを得ることを目的としており、すでにTEST 0004に関するデータ報告で述べたように、破断口面積は実炉の想定破断口面積の幾何学的縮尺値に対して過大に設定されている。

昭和54年12月までに実施した試験の試験条件の要約をTable 3.1に、本試験の初期条件、データ収録の状況、試験中の物質・エネルギー移動の要約をTable 3.2～3.4にそれぞれ示す。

圧力容器の昇温・昇圧は3月29日、30日の2日間にわたって行った。放出に先立ち、ラブチャディスクの展開を確実にすることを目的として放出配管の末端部から窒素ガスを注入した。まず主放出弁(AV-1)を閉じ冷水放出弁(CV-2)を開いて主放出弁下流側を約2.5MPaまで減圧し、放出配管内に窒素ガスを注入して圧力容器とほぼ等しい圧力まで加圧し、再び主放出弁を開いて放出配管内の流体の温度上昇を待った。放出開始前後の運転記録をFig.3.1に、圧力容器、放出配管内の初期温度分布をFig.3.2に、ドライウェル、ウェットウェル内の初期および放出終了後の温度分布をそれぞれFig.3.3、Fig.3.4に示す。

試験結果の定量的評価・解析は後報にゆずり、ここでは結果の概要のみを述べる。

放出開始前に窒素ガスの充てんを行ったため、放出配管内の初期水位は明らかでない。放出配管内の初期温度は飽和温度を最大11°C下回った。放出開始直後の放出配管、圧力容器内の圧力・温度挙動はTEST 0004の結果と良く一致した。まず、約0.5秒間にわたり放出配管内に最大3.3MPaの一時的減圧が発生した。また圧力容器蒸気ドーム内には、液相の沸騰遅れのため約0.8秒間にわたり最大0.5MPaの一時的減圧が発生した。圧力容器の水位は放出開始後約2.2秒で放出配管入口レベルに達し、以後放出流体のクオリティが増大した。

放出初期のドライウェル圧力上昇率(放出開始からベントクリアリングまでの期間の平均値)は約155kPa/sであり、TEST 0004と同様に、実炉の再循環系配管両端破断事故時の想定値である165～200kPa/sには達しなかった。

ベントクリアリングは放出開始0.78秒後に各ベント管においてほぼ同時に生じた。ベントクリアリング後プール内に形成された気泡の下端は、ベント管出口の少くとも0.9m下方に達した。ベントクリアリング直後のプール内圧力上昇(LOCA時の動荷重のうち、いわゆるジェット荷重ないし気泡荷重に相当する)はプール底面において最も大きく、約102kPaであった。

ドライウェルからウェットウェルへの空気のキャリオーバは放出開始後約2.0秒間にわたり活発であり、ここに放出開始後約5秒間はこれに伴うプール水位の上昇が顕著であった。クリアリング直後から約0.6秒間は水面はほぼ平坦に上昇したが、以後は乱れが発生し、水位は不均一となった。プールの平均水位は放出開始後約1.6秒で極大値をとり以後低下したが、水面のブレークスルーが発生した後プール水はフロス状の2相流を形成して再び上昇し、放出開始

後約4秒から5秒にかけてプール水位が最高となつた。最高水位は計測点の位置によって異り、計測点L1ではプール底面から14.75m(初期水位から7.46m上方)以上の高さまでプール水が到達した。また、プールスウェルに際してウエットウェル気相部の圧力がベント管内の圧力を一時的に上回り、ベント管VP3に設けられたバキュームブレーカが放出開始後1.5秒から1.9秒にかけて開き、最大開度に達した。

放出開始前のドライウェル温度は層状に分布し、最大20°Cの不均一を示した。放出開始後約20秒で温度は均一になり、飽和温度にほぼ一致する値となつた。ドライウェル内での気液分離の結果、放出流体の一部がドライウェル底面に蓄積した。試験中の蓄積水量は、全放出量とプール水量増加との差から約1300kgと評価され、これは全放出量の約7%に相当する。

試験開始前のウエットウェル気相部温度、圧力抑制プール温度はそれぞれほぼ均一であった。試験開始後、プールスウェルによる気相部圧縮、およびベント管・ダイアフラムフロアからの熱伝達により気相部温度が上昇した。なお、プール底面から11m以下の位置にある熱電対はプールスウェルに際して冠水し、以後の出力は気相部温度を必ずしも正しく示していないと考えられる。プール水の混合は不完全であり、一般にプール底面および水面付近の温度上昇はベント管出口高さ付近の温度上昇より遅れた。

本試験における最大放出流量は約720kg/s、ベント流中の蒸気の最大重量速度は約100kg/m²-sと評価される。放出開始後約37秒から54秒にかけてベント管内にプール水が間欠的に流入した。約43秒から50秒にかけて計4回、ベント管内の水位は出口の1m以上上方に達し、プール内の圧力は典型的なチャギングの波形を示した。なお、本試験においてはチャギングに際してバキュームブレーカは動作しなかつた。

放出開始後約72秒で主放出弁を全閉とし、試験を終了した。

謝　　辞

本報告は、先に作成した非公開資料JAERI-memo 8325の内容に検討・修正を加えたものを科学技術庁原子力局技術振興課の指導のもとに公開に付するものである。

試験装置の管理、ならびに試験の実施は、原研安全工学部安全性試験技術室の関口一雄室長、三森武男氏、宮本善夫氏、千葉辰夫氏、伊藤秀雄氏、大崎秀機氏、塚本導雄氏が担当した。本報告の刊行にあたり、ここに深甚なる謝意を表する。

後約4秒から5秒にかけてプール水位が最高となつた。最高水位は計測点の位置によって異り、計測点L1ではプール底面から14.75m(初期水位から7.46m上方)以上の高さまでプール水が到達した。また、プールスウェルに際してウエットウェル気相部の圧力がベント管内の圧力を一時的に上回り、ベント管VP3に設けられたバキュームブレーカが放出開始後1.5秒から1.9秒にかけて開き、最大開度に達した。

放出開始前のドライウェル温度は層状に分布し、最大20°Cの不均一を示した。放出開始後約20秒で温度は均一になり、飽和温度にほぼ一致する値となつた。ドライウェル内での気液分離の結果、放出流体の一部がドライウェル底面に蓄積した。試験中の蓄積水量は、全放出量とプール水量増加との差から約1300kgと評価され、これは全放出量の約7%に相当する。

試験開始前のウエットウェル気相部温度、圧力抑制プール温度はそれぞれほぼ均一であった。試験開始後、プールスウェルによる気相部圧縮、およびベント管・ダイアフラムフロアからの熱伝達により気相部温度が上昇した。なお、プール底面から11m以下の位置にある熱電対はプールスウェルに際して冠水し、以後の出力は気相部温度を必ずしも正しく示していないと考えられる。プール水の混合は不完全であり、一般にプール底面および水面付近の温度上昇はベント管出口高さ付近の温度上昇より遅れた。

本試験における最大放出流量は約720kg/s、ベント流中の蒸気の最大重量速度は約100kg/m²-sと評価される。放出開始後約37秒から54秒にかけてベント管内にプール水が間欠的に流入した。約43秒から50秒にかけて計4回、ベント管内の水位は出口の1m以上上方に達し、プール内の圧力は典型的なチャギングの波形を示した。なお、本試験においてはチャギングに際してバキュームブレーカは動作しなかつた。

放出開始後約72秒で主放出弁を全閉とし、試験を終了した。

謝　　辞

本報告は、先に作成した非公開資料JAERI-memo 8325の内容に検討・修正を加えたものを科学技術庁原子力局技術振興課の指導のもとに公開に付するものである。

試験装置の管理、ならびに試験の実施は、原研安全工学部安全性試験技術室の関口一雄室長、三森武男氏、宮本善夫氏、千葉辰夫氏、伊藤秀雄氏、大崎秀機氏、塚本導雄氏が担当した。本報告の刊行にあたり、ここに深甚なる謝意を表する。

(As of January 1980)

Table 3.1 Test Matrix

Test Number	DISCHARGE CONDITIONS				INITIAL CONDITIONS						Number of Breaker Functions	Date of Performance	Ref. Report Number JAERI-M	REMARKS	
	Disch. Fluid	Nozzle Diam.	Pipe Inlet Diam.	Time of Blowdown Prepurge (%)	Pressure Vessel (kPa)	Water Temp. (°C)	Pool Level (m)	Vent Temp. (°C)	Sub. Temp. (°C)	Vents (m)					
0001	water	100	2.105	none	ca. 600			22.5	3.342	7	yes	2/18/79		Shakedown test performed by Hitachi Ltd.	
0002	water	100	2.105	none	7015	286	6.28	24.6	3.867	7	yes	2/21	8598	Excluded from reporting. Shakedown test performed by Hitachi Ltd.	
0003	water	100	2.105	none	6976	286	7.35	27.8	3.802	7	yes	2/23	present	Shakedown test performed by Hitachi Ltd.	
0004	water	200	2.105	none	7005	286	6.89	9.9	3.852	7	yes	2/28	present	Shakedown test performed by Hitachi Ltd.	
1101	water	200	2.105	none	72	7020	286	7.17	29.9	3.632	7	yes	3/30	present	
2101	water	74	2.105	none	343	6966	287	7.99	14.2	3.345	7	yes	4/27	present	
3101	water	74	2.105	23	298	6887	286	7.79	18.9	3.347	7	yes	5/25	present	
3102	water	200	2.105	98	68.5	6966	287	7.73	33.2	3.622	7	yes	6/29	present	
1201	steam	200	9.105	none	85	6894	286	5.71	52.3	3.327	7	yes	8/24		
1202	steam	240	9.105	none	89.0	6976	286	5.44	53.5	3.342	7	yes	9/14		
1203	steam	220	9.105	none	91.9	6974	286	5.06	53.9	3.340	7	yes	10/05		
1204	steam	220	9.105	none	89.9	6971	286	5.32	18.7	3.338	7	yes	10/22		
1205	steam	220	9.105	none	94.5	6966	287	5.77	63.5	3.350	7	no	11/09		
1206	steam	220	9.105	none	85.1	6966			1.962	7	yes	11/29			

TEST NO. = ABCD

A = 1 Pool Swell Test

A = 2 Condensation Oscillation Test without Prepurge
A = 3 Condensation Oscillation Test with Prepurge

B = 1 Water Blowdown

B = 2 Steam Blowdown
B = 3 Air Blowdown

CD = Sequential Number

Table 3.2 Test Specifications

FULL-SCALE MARK II CRT DATA SHEET (TEST SPECIFICATIONS)

TEST NUMBER 1101 DATE OF PERFORMANCE Mar. 30, 1979

(A) SPECIFICATIONS FOR TEST FACILITY CONFIGURATION AND TEST PROCEDURE

- (1) Diameter of Discharge Nozzle (mm) 200
 (2) Inlet Level of Blowdown Pipe (m) 2.105
 (3) Percentage of Prepurge, Specified/Performed (%) None
 (4) Number of Open Vent Pipes 7
 (5) Vacuum Breaker Functionability yes
-

(B) SPECIFICATIONS FOR INITIAL CONDITIONS

(1) Pressure Vessel

Item	Specified	Performed
Pressure (kPa)	6966	7020 *
Temperature (°C)	285	285.8
Water Level (m)	5.0	7.160

(2) Test Containment

Item		Specified	Performed	
			Before Prepurge	Before Break
Pressure (kPa)	Drywell	101		101
	Wetwell	101		101
Pool Temp. (°C)		25		29.9
Pool Level (m)		7.5		7.290

* Pressure vessel slightly leaked before the test.

(C) AMBIENT CONDITIONS

Pressure (kPa) _____ Temperature (°C) 17.4

Table 3.3 Summary of Data Recording

(A) Structure of Computer Processed Tapes

Tape No.		11010		11011		11012	
File No.	Index	Contents	Period (s)	Contents	Period (s)	Contents	Period (s)
1		Tape No. Heading		Tape No. Heading		Tape No. Heading	
2	1	R0		R0		R0	
3	2	R1		R1		R1	
4	3	R2		R2		R2	
5	4	Data	-14- 106	Data	-11- 94	Data	-13- 93
6	5						

(B) Structure of PCM Tape

Record No.	Tape Counter Indication	Time Code	Contents
1	1300 - 1353	17°45'09" -	R0
2	1353 - 1420	17°47'06" -	R1
3	1420 - 1501	17°48'36" -	R2
4	1501 - 2040	17°54'17" -	Data
5			
6			

Notes:

- Last digit of tape number indicates contents of the tape;
 - 0 Online data recorded by the system computer.
 - 1 Data transferred from PCM recorder track 1.
 - 2 Data transferred from PCM recorder track 2.
- R0, R1, R2 are records for calibration of data channels;
 - R0 Zero scale calibration outputs.
 - R1 Full scale calibration outputs.
 - R2 Initial values.

Table 3.4 Initial and Final Conditions

TEST NUMBER 1101 DATE OF PERFORMANCE Mar.30,'79

PRESSURE VESSEL	Unit	Before Test	100 s after* Break	Change
Pressure	kPa	7020		
Averaged Liquid Temperature	°C	285.8	142.3	
Max./Min. Liquid Temperature	°C	286.1/285.4		
Averaged Steam Temperature	°C	285.8	166.0	
Sat. Press. Based on Liquid Temp.	kPa	7001		
Liquid Level Based on PVDS-001	m	7.160	0.452	
Liquid Level Based on PVDS-002 - 006	m	7.160	0.423	
Mass of Water	kg	2.08×10^4	2.20×10^3	-1.86×10^4
Energy of Water	kJ	2.68×10^7	1.46×10^6	-2.53×10^7
BLOWDOWN PIPE				
Max./Min. Temperature	°C	276.6/274.5		
DRYWELL				
Pressure	kPa	101	(231)	
Sat. Temp. Based on Pressure	°C		127.5	
Averaged Gas Phase Temperature	°C	39.3	130.4	
Max./Min. Gas Phase Temperature	°C	49.0/27.9	131.2/127.1	
Liquid Level	m		0 - 0.042	
VENT PIPES				
Max./Min. Inlet Temperature	°C	18.1/17.7	131.3/70.5	
Max./Min. Outlet Temperature	°C	30.4/30.3	53.3/46.3	
WETWELL				
Pressure	kPa	101	(226)	
Averaged Pool Temperature	°C	29.9	50.2	
Max./Min. Pool temperature	°C	30.4/29.3	54.1/45.3	
Averaged Airspace Temperature	°C	18.1	44.4	
Max./Min. Airspace Temperature	°C	18.5/17.8	54.5/34.5	
Liquid Level	m	7.290	7.924	
Mass of Water	kg	1.95×10^5	2.12×10^5	1.70×10^4
Energy of Water	kJ	2.44×10^7	4.46×10^7	2.02×10^7
Mass of Air	kg			

REMARKS

* Numbers in parentheses are data measured after opening the equalizer valve between drywell and wetwell.




Fig. 3.1 Operation Records




Fig. 3.2 Initial Temperature Distribution in Primary System





Fig. 3.3 * Initial and Final Temperature Distributions in Drywell

* 100 seconds after break



* 100 seconds after break

Fig. 3.4 Initial and Final Temperature Distributions in Wetwell

Long Term Plots of Data

Long Term Plot Specification

Period 0 - 100 s

Plot No.	Recording System	Recording Rate (data/s)	Sampling Rate for Plots	Interval for Envelope Plots (s)	Remarks
L-0-1 to 37	Computer	50.00	1/3		
L-1-1 to 32	PCM Track-1	455.56	1/26	1.199	
L-2-1 to 14	PCM Track-2	455.56	1/26	1.199	

List of Long Term Plots

Computer Recorded Channels

Plot L-0-1	Actuation Signals	
L-0-2	Pressures in Pressure Vessel and Blowdown Pipe	
L-0-3	Pressures in Drywell and Wetwell Airspace	
L-0-4	DP over Pressure Vessel	
L-0-5	DP across Wetwell Pool Surface	
L-0-6	DP across Diaphragm Floor	
L-0-7	Temperatures in Pressure Vessel	
L-0-8	Temperatures in Blowdown Pipe	
L-0-9	Temperatures in Drywell	(DWTS - 101-103)
L-0-10	Temperatures in Drywell	(DWTS - 201-203)
L-0-11	Temperatures in Drywell	(DWTS - 301-302)
L-0-12	Temperatures in Vent Pipe	(VP1)
L-0-13	Temperatures in Vent Pipe	(VP2)
L-0-14	Temperatures in Vent Pipe	(VP3)
L-0-15	Temperatures in Wetwell	(WWTS - 101-104)
L-0-16	Temperatures in Wetwell	(WWTS - 108-108)
L-0-17	Temperatures in Wetwell	(WWTS - 201-204)
L-0-18	Temperatures in Wetwell	(WWTS - 208-208)
L-0-19	Temperatures in Wetwell	(WWTS - 301-304)
L-0-20	Temperatures in Wetwell	(WWTS - 308-308)
L-0-21	Temperatures in Wetwell	(WWTS - 401-404)
L-0-22	Temperatures in Wetwell	(WWTS - 408-408)
L-0-23	Water Level in Pressure Vessel	
L-0-24	Water Level in Drywell	
L-0-25	Water Level in Vent Pipe	(VP1)
L-0-26	Water Level in Vent Pipe	(VP2)
L-0-27	Water Level in Vent Pipe	(VP3)
L-0-28	Water Level in Vent Pipe	(VP4)
L-0-29	Water Level in Vent Pipe	(VP5)
L-0-30	Water Level in Wetwell	(WWLS - 104-116)
L-0-31	Water Level in Wetwell	(WWLS - 201-216)
L-0-32	Water Level in Wetwell	(WWLS - 303-315)
L-0-33	Water Level in Wetwell	(WWLS - 401-416)
L-0-34	Water Level in Wetwell	(WWLS - 503-515)
L-0-35	Water Level in Wetwell	(WWLS - 604-616)
L-0-36	Water Level in Wetwell	(WWLS - 704-716)
L-0-37	Water Level in Wetwell	(WWLS - 804-816)

List of Long Term Plots (Continued)

PCM Track-1 Channels


Plot L-1-1 Pressures in Drywell and Wetwell Airspace
 L-1-2 Pressure in Vent Pipe (VPPF-101)
 L-1-3 Pressure in Vent Pipe (VPPF-201)
 L-1-4 Pressure in Vent Pipe (VPPF-301)
 L-1-5 Pressure in Vent Pipe (VPPF-302)
 L-1-6 Pressure in Vent Pipe (VPPF-303)
 L-1-7 Pressure in Vent Pipe (VPPF-401)
 L-1-8 Pressure in Vent Pipe (VPPF-501)
 L-1-9 Pressure in Vent Pipe (VPPF-502)
 L-1-10 Pressure in Vent Pipe (VPPF-503)
 L-1-11 Pressure in Wetwell (WWPF-101)
 L-1-12 Pressure in Wetwell (WWPF-102)
 L-1-13 Pressure in Wetwell (WWPF-103)
 L-1-14 Pressure in Wetwell (WWPF-104)
 L-1-15 Pressure in Wetwell (WWPF-105)
 L-1-16 Pressure in Wetwell (WWPF-106)
 L-1-17 Pressure in Wetwell (WWPF-107)
 L-1-18 Pressure in Wetwell (WWPF-201)
 L-1-19 Pressure in Wetwell (WWPF-202)
 L-1-20 Pressure in Wetwell (WWPF-203)
 L-1-21 Pressure in Wetwell (WWPF-301)
 L-1-22 Pressure in Wetwell (WWPF-302)
 L-1-23 Pressure in Wetwell (WWPF-303)
 L-1-24 Pressure in Wetwell (WWPF-401)
 L-1-25 Pressure in Wetwell (WWPF-402)
 L-1-26 Pressure in Wetwell (WWPF-501)
 L-1-27 Pressure in Wetwell (WWPF-502)
 L-1-28 Pressure in Wetwell (WWPF-602)
 L-1-29 Pressure in Wetwell (WWPF-702)
 L-1-30 Strain of Vent Pipe Brace (VPSF-101)
 L-1-31 Strain of Vent Pipe Brace (VPSF-102)
 L-1-32 Strain of Vent Pipe Brace (VPSF-201)

PCM Track-2 Channels

Plot L-2-1 Acceleration of Vent Pipe Outlet (VPAF-101)
 L-2-2 Acceleration of Vent Pipe Outlet (VPAF-201)
 L-2-3 Acceleration of Vent Pipe Outlet (VPAF-202)
 L-2-4 Acceleration of Containment Structure (WWAF-005)
 L-2-5 Acceleration of Containment Structure (WWAF-006)
 L-2-6 Acceleration of Containment Structure (WWAF-007)
 L-2-7 Acceleration of Containment Structure (WWAF-008)
 L-2-8 Acceleration of Containment Structure (WWAF-009)
 L-2-9 Acceleration of Containment Structure (WWAF-010)
 L-2-10 Acceleration of Containment Structure (WWAF-011)
 L-2-11 Acceleration of Containment Structure (WWAF-012)
 L-2-12 Phase Boundary Signals (WWLF-101-108)
 L-2-13 Phase Boundary Signals (WWLF-201-209)
 L-2-14 Phase Boundary Signals (WWLF-301-308)

TEST 1101

FULL-SCALE MARK II CRT




Plot L-0-1 Actuation Signals

TEST 1101

FULL-SCALE MARK II CRT

- PVPS-001 VESSEL STEAM DOME
- △ PVPS-002 VESSEL STEAM DOME
- BPPS-001 BLOWDOWN PIPE (8.4M FROM OUTL.)
- × BPPS-002 BLOWDOWN PIPE 10.9M FROM OUTL.




Plot L-0-2 Pressures in Vessel and Blowdown Pipe

TEST 1101

○ DWPS-001 DRYWELL
 △ WWPS-001 WETWELL AIRSPACE (15.0M ABOVE BOTT.)

FULL-SCALE MARK II CRT




Plot L-0-3 Pressures in Drywell and Wetwell Airspace

TEST 1101

○ PVDS-001 DP OVER VESSEL TEL = 0.0M +9.2M
 △ PVDS-002 DP OVER VESSEL TEL = 0.0M +2.6M
 + PVDS-003 DP OVER VESSEL TEL = -2.2M +4.2M
 ✕ PVDS-004 DP OVER VESSEL TEL = -3.8M -5.8M

FULL SCALE MARK II CRT


◊ PVDS-005 DP OVER VESSEL TEL = +5.4M +7.4M
 ♦ PVDS-006 DP OVER VESSEL TEL = +7.0M +9.2M




Plot L-0-4 DP over Vessel

TEST 1101
© WWDS-001 DP OVER POOL (EL = 4.5M -15.5M)


FULL-SCALE MARK II CRT




Plot L-0-5 DP across Pool Surface



Plot L-0-6 DP across Diaphragm Floor



Plot L-0-7 Temperatures in Vessel




Plot L-0-8 Temperatures in Blowdown Pipe

TEST 1101

FULL-SCALE MARK II CRT

- DWTS-101 DRYWELL (0.5M ABOVE DF)
- △ DWTS-102 DRYWELL (2.5M ABOVE DF)
- + DWTS-103 DRYWELL (4.5M ABOVE DF)




Plot L-0-9 Temperatures in Drywell

TEST 1101

FULL-SCALE MARK II CRT


- DWTS-201 DRYWELL (0.5M ABOVE DF)
- △ DWTS-202 DRYWELL (2.5M ABOVE DF)
- + DWTS-203 DRYWELL (4.5M ABOVE DF)



Plot L-0-10 Temperatures in Drywell

TEST 1101
 ○ DWTS-301 DRYWELL (0.5M ABOVE DF)
 △ DWTS-302 DRYWELL (3.5M ABOVE DF)


FULL-SCALE MARK II CRT



Plot L-0-11 Temperatures in Drywell

TEST 1101
 ○ VPTS-101 VPI (1.0M ABOVE OUTL.)
 △ VPTS-102 VPI (11.5M ABOVE OUTL.)

FULL-SCALE MARK II CRT




Plot L-0-12 Temperatures in Vent Pipe.

TEST 1101

○ VPTS-201 VP2 (0.5M ABOVE OUTL.)
 △ VPTS-202 VP2 (11.5M ABOVE OUTL.)

FULL-SCALE MARK II CRT




Plot L-0-13 Temperatures in Vent Pipe

TEST 1101

○ VPTS-301 VP3 (0.5M ABOVE OUTL.)
 △ VPTS-302 VP3 (11.5M ABOVE OUTL.)


FULL-SCALE MARK II CRT



Plot L-0-14 Temperatures in Vent Pipe

TEST 1101


FULL-SCALE MARK II CRT




Plot L-0-15 Temperatures in Wetwell

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-16 Temperatures in Wetwell




Plot L-0-17 Temperatures in Wetwell



Plot L-0-18 Temperatures in Wetwell

TEST 1101
 ○ WHTS-301 WETWELL (T3, 1.0M ABOVE BOTT.)
 △ WHTS-302 WETWELL (T3, 3.0M ABOVE BOTT.)
 + WHTS-303 WETWELL (T3, 5.0M ABOVE BOTT.)
 × WHTS-304 WETWELL (T3, 7.0M ABOVE BOTT.)


FULL-SCALE MARK II CRT



Plot L-0-19 Temperatures in Wetwell

TEST 1101
 ○ WHTS-305 WETWELL (T3, 9.0M ABOVE BOTT.)
 △ WHTS-306 WETWELL (T3, 11.0M ABOVE BOTT.)
 + WHTS-307 WETWELL (T3, 13.0M ABOVE BOTT.)
 × WHTS-308 WETWELL (T3, 15.0M ABOVE BOTT.)

FULL-SCALE MARK II CRT




Plot L-0-20 Temperatures in Wetwell

TEST 1101

FULL-SCALE MARK II CRT

○ WHTS-401 WETWELL (T4, 1.0M ABOVE BOTT.)
 △ WHTS-402 WETWELL (T4, 3.0M ABOVE BOTT.)
 + WHTS-403 WETWELL (T4, 5.0M ABOVE BOTT.)
 × WHTS-404 WETWELL (T4, 7.0M ABOVE BOTT.)




Plot L-0-21 Temperatures in Wetwell

TEST 1101

FULL-SCALE MARK II CRT


○ WHTS-405 WETWELL (T4, 9.0M ABOVE BOTT.)
 △ WHTS-406 WETWELL (T4, 11.0M ABOVE BOTT.)
 + WHTS-407 WETWELL (T4, 13.0M ABOVE BOTT.)
 × WHTS-408 WETWELL (T4, 15.0M ABOVE BOTT.)



Plot L-0-22 Temperatures in Wetwell

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-23 Water Level in Vessel

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-24 Water Level in Drywell

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-25 Water Level in Vent Pipe

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-26 Water Level in Vent Pipe

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-27 Water Level in Vent Pipe

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-28 Water Level in Vent Pipe

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-29 Water Level in Vent Pipe

TEST 1101

FULL-SCALE MARK II CRT




Plot L-0-30 Water Level in Wetwell

JAERI-M 8763

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-31 Water Level in Wetwell

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-32 Water Level in Wetwell

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-33 Water Level in Wetwell

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-34 Water Level in Wetwell

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-35 Water Level in Wetwell

TEST 1101


FULL-SCALE MARK II CRT




Plot L-0-36 Water Level in Wetwell

TEST 1101


FULL-SCALE MARK II CRT



Plot L-0-37 Water Level in Wetwell



Plot L-1-1 Pressures in Drywell and Wetwell Airspace




Plot L-1-2 Pressure in Vent pipe

Pressure in Vent pipe

TEST 1101
O VPPF-201 VP2 (0.5M ABOVE OUTL.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-3 Pressure in Vent pipe

TEST 1101
O VPPF-301 VP3 (0.5M ABOVE OUTL.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-4 Pressure in Vent pipe

TEST 1101
© VPPF-302 VP3 (6.0M ABOVE OUTL.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-5 Pressure in Vent pipe

TEST 1101
© VPPF-303 VP3 (11.5M ABOVE OUTL.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-6 Pressure in Vent pipe

TEST 1101
⑤ VPPF-401 VP4 (0.5M ABOVE OUTL.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-7 Pressure in Vent pipe

TEST 1101
⑤ VPPF-501 VP5 (0.5M ABOVE OUTL.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-8 Pressure in Vent pipe

TEST 1101
© VPPF-502 VPS (6.0M ABOVE OUTL.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-9 Pressure in Vent pipe

TEST 1101
© VPPF-503 VPS (111.5M ABOVE OUTL.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-1-10 Pressure in Vent pipe

JAERI-M 8763

TEST 1101
© WWPF-101 POOL BOTT., UNDER VP1
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-11 Pressure in Wetwell

TEST 1101
© WWPF-102 POOL BOTT., UNDER VP2
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-1-12 Pressure in Wetwell

JAERI-M 8763

TEST 1101
© WWPF-103 POOL BOTT., UNDER VP3
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-13 Pressure in Wetwell

TEST 1101
© WWPF-104 POOL BOTT., UNDER VP4
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-14 Pressure in Wetwell

TEST 1101
© WWPF-105 POOL BOTT., UNDER VPS
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-15 Pressure in Wetwell

TEST 1101
© WWPF-106 POOL BOTT., BETH. VPI, VPS & PEDESTAL
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-16 Pressure in Wetwell

TEST 1101
① WWPF-107 POOL BOTT., BETW. VP2 & VP3
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-17 Pressure in Wetwell

TEST 1101
① WWPF-201 WALL BESIDE VP2 (P1, 1.8M ABOVE BOTT.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-1-18 Pressure in Wetwell

JAERI-M 8763

TEST 1101
④ WWPF-202 WALL BESIDE VP2 (PI. 3.6M ABOVE BOTT.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-19 Pressure in Wetwell

TEST 1101
④ WWPF-203 WALL BESIDE VP2 (PI. 6.0M ABOVE BOTT.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-20 Pressure in Wetwell

TEST 1101

○ WWPF-301 WALL BESIDE VP3 (P2, 1.8M ABOVE BOTT.)
PLOT WITH ENVELOPE




Plot L-1-21 Pressure in Wetwell

TEST 1101

○ WWPF-302 WALL BESIDE VP3 (P2, 3.6M ABOVE BOTT.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-1-22 Pressure in Wetwell

TEST 1101

© WWPF-303 WALL BESIDE VP3 (P2, 6.0M ABOVE BUTT.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-1-23 Pressure in Wetwell

TEST 1101

© WWPF-401 SHELL BESIDE VP3 (P3, 1.8M ABOVE BUTT.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-24 Pressure in Wetwell

TEST 1101
① WWPF-402 SHELL BESIDE VP3 (P3, 3.6M ABOVE BOTT.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-25 Pressure in Wetwell

TEST 1101
① WWPF-501 SHELL BESIDE VP4 (P4, 1.8M ABOVE BOTT.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-1-26 Pressure in Wetwell

JAERI-M 8763

TEST 1101

© WWPF-602 SHELL BESIDE VP4 (P4, 3.6M ABOVE BOTT.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-1-27 Pressure in Wetwell

TEST 1101

© WWPF-602 WALL BESIDE VP4 (P5, 3.6M ABOVE BOTT.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-28 Pressure in Wetwell

TEST 1101
① WMPF-702 WALL BESIDE VP7 (P6. 3.6M ABOVE BOTT.)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-29 Pressure in Wetwell

TEST 1101
① VPSF-101 LOWER BRACE BETW. VP1 & WALL
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-30 Strain of Vent pipe Brace

TEST 1101
© VPSF-102 LOWER BRACE BETW. VPI & VP2
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-1-31 Strain of Vent pipe Brace

TEST 1101
© VPSF-201 UPPER BRACE BETW. VPI & PEDESTAL
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-1-32 Strain of Vent pipe Brace


JAERI-M 8763

TEST 1101
① VPAF-101 VP2 OUTL. (00EG)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT



Plot L-2-1 Acceleration of Vent pipe Outlet




Plot L-2-2 Acceleration of Vent pipe Outlet

JAERI-M 8763

TEST 1101
◎ VPAF-2C2 VPS OUTL. (90DEG)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-2-3 Acceleration of Vent pipe Outlet


TEST 1101
◎ WHAF-005 SHELL BESIDE VPS (3.0M ABOVE BOTT.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-2-4 Acceleration of Containment Structure

TEST 1101
⑤ WWAFF-006 SHELL (BESIDE VP3 16.0M ABOVE BOTT.)
PLOT WITH ENVELOPE



Plot L-2-5 Acceleration of Containment Structure

TEST 1101
⑥ WWAFF-007 SHELL (BESIDE VP4 13.0M ABOVE BOTT.)
PLOT WITH ENVELOPE




Plot L-2-6 Acceleration of Containment Structure

JAERI-M 8763

TEST 1101

G WWAFF-008 SHELL BESIDE VP4 (6.0M ABOVE BOTT.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-2-7 Acceleration of Containment Structure

TEST 1101

G WWAFF-009 PEDESTAL (3.0M ABOVE BOTT.)
PLOT WITH ENVELOPE

FULL-SCALE MARK II CRT




Plot L-2-8 Acceleration of Containment Structure

JAERI-M 8763

TEST 1101
@ WWAFF-010 PEDESTAL (6.0M ABOVE BOTTOM)
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-2-9 Acceleration of Containment Structure

TEST 1101
@ WWAFF-011 SHELL AT CP LEVEL + 100G.
PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-2-10 Acceleration of Containment Structure

TEST 1101
 © WWAFF-012 SHELL RT OF LEVEL (900EG)
 PLOT WITH ENVELOPE


FULL-SCALE MARK II CRT



Plot L-2-11 Acceleration of Containment Structure

TEST 1101


FULL-SCALE MARK II CRT



Plot L-2-12 Phase Boundary Signals

TEST 1101


FULL-SCALE MARK II CRT



Plot L-2-13 Phase Boundary Signals

TEST 1101

FULL-SCALE MARK II CRT



Plot L-2-14 Phase Boundary Signals

Short Term Plots of Data

Short Term Plot Specification

Period 0 - 5 sObjective : Detailed Presentation of Pool Swell. High and Medium Steam Flux

Condensation Oscillation.

 Chugging.

Plot No.	Recording System	Recording Rate (data/s)	Sampling Rate for Plots	Remarks
S-0-1 to 24	Computer	50.00	1/1	
S-1-1 to 14	PCM Track-1	455.56	1/1	
S-2-1 to 14	PCM Track-2	455.56	1/1	

List of Short Term Plots**Computer Recorded Channels**

Plot S-0-1	Actuation Signals	
S-0-2	Pressures in Pressure Vessel and Blowdown Pipe	
S-0-3	Pressures in Drywell and Wetwell Airspace	
S-0-4	DP over Pressure Vessel	
S-0-5	Temperatures in Pressure Vessel	
S-0-6	Temperatures in Blowdown Pipe	
S-0-7	Temperatures in Drywell	(DWTS-101-103)
S-0-8	Temperatures in Drywell	(DWTS-201-203)
S-0-9	Temperatures in Drywell	(DWTS-301-302)
S-0-10	Temperatures in Vent Pipe	(VPTS-101-102)
S-0-11	Temperatures in Vent Pipe	(VPTS-201-202)
S-0-12	Temperatures in Vent Pipe	(VPTS-301-302)
S-0-13	Temperatures in Wetwell	(WWTS-101-104)
S-0-14	Temperatures in Wetwell	(WWTS-105-108)
S-0-15	Temperatures in Wetwell	(WWTS-201-204)
S-0-16	Temperatures in Wetwell	(WWTS-205-208)
S-0-17	Temperatures in Wetwell	(WWTS-301-304)
S-0-18	Temperatures in Wetwell	(WWTS-305-308)
S-0-19	Temperatures in Wetwell	(WWTS-401-404)
S-0-20	Temperatures in Wetwell	(WWTS-405-408)
S-0-21	Water Level in Drywell	(DWLS-001-004)
S-0-22	Water Level in Vent Pipe	(VPLS-101-205)
S-0-23	Water Level in Vent Pipe	(VPLS-301-405)
S-0-24	Water Level in Vent Pipe	(VPLS-501-505)

PCM Track-1 Channels

Plot S-1-1	Pressures in Drywell and Wetwell Airspace	
S-1-2	Pressure in Vent Pipe	(VPPF-101, 201, 401)
S-1-3	Pressure in Vent Pipe	(VPPF-301, 302, 303)
S-1-4	Pressure in Vent Pipe	(VPPF-501, 502, 503)
S-1-5	Pressure in Wetwell	(VPPF-102, 201, 202, 203)
S-1-6	Pressure in Wetwell	(WWPF-103, 301, 302, 303)
S-1-7	Pressure in Wetwell	(WWPF-103, 401, 402)
S-1-8	Pressure in Wetwell	(WWPF-104, 501, 502)
S-1-9	Pressure in Wetwell	(WWPF-101, 106)
S-1-10	Pressure in Wetwell	(WWPF-105, 107)
S-1-11	Pressure in Wetwell	(WWPF-602, 702)
S-1-12	Strain of Vent Pipe Brace	(VPSF-101)
S-1-13	Strain of Vent Pipe Brace	(VPSF-102)
S-1-14	Strain of Vent Pipe Brace	(VPSF-201)


PCM Track-2 Channels

Plot S-2-1	Acceleration of Vent Pipe Outlet	(VPAF-101)
S-2-2	Acceleration of Vent Pipe Outlet	(VPAF-201)
S-2-3	Acceleration of Vent Pipe Outlet	(VPAF-202)
S-2-4	Acceleration of Containment Structure	(WWAF-005)
S-2-5	Acceleration of Containment Structure	(WWAF-006)
S-2-6	Acceleration of Containment Structure	(WWAF-007)
S-2-7	Acceleration of Containment Structure	(WWAF-008)
S-2-8	Acceleration of Containment Structure	(WWAF-009)
S-2-9	Acceleration of Containment Structure	(WWAF-010)
S-2-10	Acceleration of Containment Structure	(WWAF-011)
S-2-11	Acceleration of Containment Structure	(WWAF-012)
S-2-12	Phase Boundary Signals	(WWLF-101-108)
S-2-13	Phase Boundary Signals	(WWLF-201-209)
S-2-14	Phase Boundary Signals	(WWLF-301-308)

JAERI-M 8763

TEST 1101

FULL-SCALE MARK II CRT




Plot S-0-1 Actuation Signals

TEST 1101

FULL-SCALE MARK II CRT

- + PVPS-001 VESSEL STEAM DOME
- △ PVPS-002 VESSEL STEAM DOME
- BPPS-001 BLOWDOWN PIPE (8.4M FROM OUTL.)
- × BPPS-002 BLOWDOWN PIPE (0.9M FROM OUTL.)




Plot S-0-2 Pressures in Pressure Vessel and Blowdown Pipe

JAERI-M 8763

TEST 1101
 ○ DWPS-001 DRYWELL
 △ WWPS-001 WETWELL AIRSPACE (15.0M ABOVE BOTT.)

FULL-SCALE MARK II CRT




Plot S-0-3 Pressures in Drywell and Wetwell Airspace



TEST 1101


FULL-SCALE MARK II CRT

○ PVDS-001 DP OVER VESSEL (EL = 0.0M - +9.2M) ♦ PVDS-005 DP OVER VESSEL (EL = +5.4M - +7.4M)
 △ PVDS-002 DP OVER VESSEL (EL = 0.0M - +2.6M) ♦ PVDS-006 DP OVER VESSEL (EL = +7.0M - +9.2M)
 + PVDS-003 DP OVER VESSEL (EL = +2.2M - +4.2M)
 ✕ PVDS-004 DP OVER VESSEL (EL = +3.8M - +5.8M)




Plot S-0-4 DP over Pressure Vessel






Plot S-0-7 Temperatures in Drywell



Plot S-0-8 Temperatures in Drywell

TEST 1101
 ○ DWTS-301 DRYWELL (0.5M ABOVE OFL)
 △ DWTS-302 DRYWELL (3.5M ABOVE OFL)


FULL-SCALE MARK II CRT



Plot S-0-9 Temperatures in Drywell

TEST 1101
 ○ VPTS-101 VP1 (0.5M ABOVE OUTL.)
 △ VPTS-102 VP1 (11.5M ABOVE OUTL.)


FULL-SCALE MARK II CRT



Plot S-0-10 Temperatures in Vent Pipe

TEST 1101
 ○ VPTS-201 VP2 (0.5M ABOVE OUTL.)
 △ VPTS-202 VP2 (11.5M ABOVE OUTL.)


FULL-SCALE MARK II CRT



Plot S-0-11 Temperatures in Vent Pipe

TEST 1101
 ○ VPTS-301 VP3 (0.5M ABOVE OUTL.)
 △ VPTS-302 VP3 (11.5M ABOVE OUTL.)

FULL-SCALE MARK II CRT




Plot S-0-12 Temperatures in Vent Pipe

JAERI-M 8763

TEST 1101


○ WHTS-101 WETWELL (TI. 1.0M ABOVE BOTT.)
 △ WHTS-102 WETWELL (TI. 3.0M ABOVE BOTT.)
 + WHTS-103 WETWELL (TI. 5.0M ABOVE BOTT.)
 × WHTS-104 WETWELL (TI. 7.0M ABOVE BOTT.)



Plot S-0-13 Temperatures in Wetwell

TEST 1101

COL	ROW	TYPE	DEPTH	TIME	WELL	TEST
Q	WWTS-105	WETWELL	(T1.	9.0M ABOVE BOTT.)		
△	WWTS-106	WETWELL	(T1.	11.0M ABOVE BOTT.)		
+	WWTS-107	WETWELL	(T1.	13.0M ABOVE BOTT.)		
×	WWTS-108	WETWELL	(T1.	15.0M ABOVE BOTT.)		




Plot S-0-14 Temperatures in Wetwell

JAERI-M 8763

TEST 1101

FULL-SCALE MARK II CRT

○ WWTS-201 WETWELL [T2. 1.0M ABOVE BOTT.]
 △ WWTS-202 WETWELL [T2. 3.0M ABOVE BOTT.]
 + WWTS-203 WETWELL [T2. 5.0M ABOVE BOTT.]
 X WWTS-204 WETWELL [T2. 7.0M ABOVE BOTT.]




Plot S-0-15 Temperatures in Wetwell


TEST 1101

FULL-SCALE MARK II CRT


○ WHTS-205 WETWELL T12, 9.0M ABOVE BOTT.)
 △ WHTS-206 WETWELL T12, 11.0M ABOVE BOTT.)
 + WHTS-207 WETWELL T12, 13.0M ABOVE BOTT.)
 * WHTS-208 WETWELL T12, 15.0M ABOVE BOTT.)




Plot S-0-16 Temperatures in Wetwell




Plot S-0-17 Temperatures in Wetwell



Plot S-0-18 Temperatures in Wetwell



Plot S-0-19 Temperatures in Wetwell




Plot S-0-20 Temperatures in Wetwell

JAERI-M 8763

TEST 1101


FULL-SCALE MARK II CRT



Plot S-0-21 Water Level in Drywell

TEST 1101


FULL-SCALE MARK II CRT



Plot S-0-22 Water Level in Vent Pipe

TEST 1101


FULL-SCALE MARK II CRT



Plot S-0-23 Water Level in Vent Pipe

TEST 1101


FULL-SCALE MARK II CRT



Plot S-0-24 Water Level in Vent Pipe

TEST 1101
 ○ DWPF-001 DRYWELL
 △ WWPF-001 WETWELL AIRSPACE (115.0M ABOVE BOTL.)

FULL-SCALE MARK II CRT




Plot S-1-1 Pressures in Drywell and Wetwell Airspace



TEST 1101
 ○ VPPF-101 VP1 : 0.5M ABOVE OUTLET
 △ VPPF-201 VP2 : 0.5M ABOVE OUTLET
 + VPPF-401 VP4 : 0.5M ABOVE OUTLET

FULL SCALE MARK II CRT

SHIFTED BY 50 KPA
 SHIFTED BY 100 KPA




Plot S-1-2 Pressure in Vent Pipe



JAERI-M 8763

TEST 1101


FULL-SCALE MARK II CRT



Plot S-1-5 Pressure in Wetwell

TEST 1101

FIGURE - SCALE MARK IN CM.




Plot S-1-6 Pressure in Wetwell

TEST 1101

TEST 1101

- ① WWPF-103 POOL BOTT.. UNDER VP3
- △ WWPF-401 SHELL BESIDE VP3 (P3. 1.8M ABOVE BOTT.)
- + WWPF-402 SHELL BESIDE VP3 (P3. 3.6M ABOVE BOTT.)

FULL-SCALE MARK II CRT




Plot S-1-7 Pressure in Wetwell

TEST 1101

TEST IT! : TUE
▲ WWPF-104 POOL BOTT., UNDER VP4
△ WWPF-501 SHELL BESIDE VP4 (P4, 1.8M ABOVE BOTT.)
+ WWPF-502 SHELL BESIDE VP4 (P4, 3.6M ABOVE BOTT.)


FULL-SCALE MARK II CRT




Plot S-1-8 Pressure in Wetwell

JAERI-M 8763

TEST 1101
○ WWPF-101 POOL BOTT.. UNDER VP1
△ WWPF-106 POOL BOTT.. BETW. VP1, VP6 & PEDESTAL SHIFTED BY 100 KPA




TEST 1101
○ WWPF-105 POOL BOTT.. UNDER VP5
△ WWPF-107 POOL BOTT.. BETW. VP2 & VP3 SHIFTED BY 100 KPA



TEST 1101

○ WWPF-602 WALL BESIDE VP4 (P5, 3.6M ABOVE BOTT.)
 △ WWPF-702 WALL BESIDE VP7 (P6, 3.6M ABOVE BOTT.) SHIFTED BY 50 KPA




Plot S-1-11 Pressure in Wetwell


TEST 1101

○ VPSF-101 LOWER BRACE BETW. VP1 & WALL

FULL-SCALE MARK II CRT
 SHIFTED BY 640 KPA




Plot S-1-12 Strain of Vent pipe Brace

TEST 1101
◎ VPSF-102 LOWER BRACE BETW. VPI & VP2FULL-SCALE MARK II CRT
SHIFTED BY 670 KPA

Plot S-1-13 Strain of Vent pipe Brace

TEST 1101
◎ VPSF-201 UPPER BRACE BETW. VPI & PEDESTAL

FULL-SCALE MARK II CRT




Plot S-1-14 Strain of Vent pipe Brace

JAERI-M 876

TEST 1101
© VPAF-101 VPS OUTL. (00EG)


FULL-SCALE MARK II CRT



Plot S-2-1 Acceleration of Vent pipe Outlet

TEST 1101
© VPAF-201 VPS OUTL. (00EG)


FULL-SCALE MARK II CRT



Plot S-2-2 Acceleration of Vent pipe Outlet

TEST 1101
© VPAF-202 VPS OUTL. (90DEG)


FULL-SCALE MARK II CRT



Plot S-2-3 Acceleration of Vent pipe Outlet


TEST 1101
© MMWF-005 SHELL BESIDE VP3 (3.0M ABOVE BOTT.)

FULL-SCALE MARK II CRT




Plot S-2-4 Acceleration of Containment Structure

TEST 1101 FULL-SCALE MARK II CRT
© WWAFF-006 SHELL BESIDE VP3 (6.0M ABOVE BOTT.)



Plot S-2-5 Acceleration of Containment Structure

TEST 1101 FULL-SCALE MARK II CRT
© WWAFF-007 SHELL BESIDE VP4 (3.0M ABOVE BOTT.)




Plot S-2-6 Acceleration of Containment Structure

TEST 1101

© WWAFF-008 SHELL BESIDE VP4 (6.0M ABOVE BOTT.)

FULL-SCALE MARK II CRT




Plot S-2-7 Acceleration of Containment Structure

TEST 1101

© WWAFF-009 PEDESTAL (3.0M ABOVE BOTT.)

FULL-SCALE MARK II CRT




Plot S-2-8 Acceleration of Containment Structure

JAERI-M 8763

TEST 1101
© WWAFF-010 PEDESTAL (6.0M ABOVE BOTT.)


FULL-SCALE MARK II CRT



Plot S-2-9 Acceleration of Containment Structure

TEST 1101
© WWAFF-011 SHELL AT OF LEVEL I 0DEG)


FULL-SCALE MARK II CRT



Plot S-2-10 Acceleration of Containment Structure

TEST 1101
© WWRF-012 SHELL AT DF LEVEL (90DEG)


FULL-SCALE MARK II CRT



Plot S-2-11 Acceleration of Containment Structure

TEST 1101

FULL-SCALE MARK II CRT




Plot S-2-12 Phase Boundary Signals

JAERI-M 8763

TEST 1101


FULL-SCALE MARK II CRT



Plot S-2-13 Phase Boundary Signals

TEST 1101

FULL-SCALE MARK II CRT



Plot S-2-14 Phase Boundary Signals